



24-Hour Service Tel: (603) 356-6767

Fax: (603) 356-5107  
Email: fxlyons@hotmail.com

### Water & Pump Services

Certified Community Water System Operator

Route 16/302  
P.O. Box 780  
Intervale NH 03845-0280

\*\*\*\*\* PROPOSAL \*\*\*\*\*

DATE: SEPTEMBER 8, 2011 - GC  
TERMS: 50% DEPOSIT  
30% COMPLETION  
20% 30 DAYS

Finance Charge 1.5%/month on unpaid balances

Rebecca Lane Water System  
Attn: Fred Jones  
PO Box 753  
Center Conway, NH 03813-0753

Dear Fred:

As a follow-up to our meeting last week and conversations, I am providing the following summary:

F.X. Lyons, Inc., had received numerous complaints of low water pressure/volume from residents on the Hunting Ridge Road side of the Rebecca Lane water system. Conditions in the pump station were checked and found to be normal; however, in checking several homes on Hunting Ridge Road, it was determined that system pressure was, in fact, diminished. After you were made aware we planned an excavation at the intersection of Route 302 and Hunting Ridge Road where a distribution valve which had previously been inoperable was located. It was our hope this valve was partially obstructed; however, after removing the valve and excavating along the 2" main parallel to route 302 it was determined that a 2" galvanized iron main exists under Route 302 less than 5' deep and in poor condition externally and severely deficient in flow rate.

The following day as we had discussed a temporary line was installed above ground through a culvert pipe on Route 302 to supplement the existing 2" galvanized which apparently has temporarily mitigated the issue.

During a routine pump house check the following week it has been determined the overall system usage has increased in the range of 40%. This could be a "new" problem or related to the 2" galvanized pipe under Route 302.

As we discussed, I have contacted the NHDOT regarding a replacement pipe under Route 302 and obtained pricing from a company for trenchless directional drilling under Route 302.

This estimated cost for this work is as follows:

- o Directional drilling
- o Excavation/cleanup/Route 302 shoulders
- o Pipe materials/values
- o Paving (intersection of Hunting Ridge Road)
- o Permits (Town of Conway, NHDOT)


Labor and materials	\$21,555.00
---------------------	-------------

Rebecca Lane Water System  
September 8, 2011  
Page 2

At this point, we have the drilling company on standby for the week following Columbus Day, but I have not proceeded further with permits, excavation contractor, etc., since this project requires a substantial amount of up-front funds. As I understand, a water system billing and probable special assessment is pending. I have attached contact information for an individual who may be able to help you with funding this project. Please let me know when you feel the system will have the adequate funds to proceed with this work.

Should you have any questions, please do not hesitate to call.

Sincerely,



Francis X. Lyons

---

Accepted

Date